

Society for IT Initiative Fund for e-Governance
Room No. 42, 9th floor, Haryana Civil Secretariat, Chandigarh
Phone No. 0172-2748142 ,2741547

Short Tender Notice

Sealed Tenders are invited for supply, installing, testing and handing over of electrical items in the Centre for e-Governance, 9th Floor, Haryana Civil Secretariat, Chandigarh. The tender may be submitted by 28.6.2010.and will be opened at 4.00 P.M. on the same day. The details of items & Wiring Diagram are available at www.haryanait.nic.in or may be collected personally from above address.

Member Secretary
Executive Committee.

DETAILS OF ELECTRICALS ITEMS.

Sr. No.	Description of Items	Make	Approx. Quantity	Price as per unit/per mtrs.
1	Bus Bar 200 AMP (cu)		01 No.	
2	Supply of 4 core cu Cable 16MM		50 Mtrs.	
3	Supply of 2 core cu Cable 10MM		80 Mtrs.	
4	Supply of 1 Core cu Cable 10 MM (RED)		90 Mtrs.	
5	Supply of 1 core cu Cable 10 MM (Black)		90 Mtrs.	
6	Supply of 1 core cu Cable 10 MM (Green)		40 Mtrs.	
7	DP Isolator 100 AMP		11 Nos	
8	DP MCB AMP		4 Nos	
9	MCB 10 AMP		20 Nos	
10	Supply of 2.5 SQ MM CU cable		300 Mtrs.	
11	Double Door 8 way MCB Box		2 Nos	
12	Double Door 2 way MCB Box		5 Nos.	
13	Supply an fixing at 100*50 PVC Channel with accessories		60 Mtrs.	
14	Laying of 3.5 X16mm Cu (Distribution panel to UPS Room)		80 Mtrs.	
15	End Termination of 3.5 core 16mm Cu cable with thimbles		4	
16	Cable laying ICx10 mm Cable from BUS Bar to UPS (input/output)		180 Mtrs.	
17	End Termination of 1C* 10mm cu cable with thimbles		48	
18	Laying of Cu cable 1c X 10mm for body earthling of UPS		40 Mtrs.	
19	Rewiring for 5 amp point including 1.5 mm cu wire for looping and 2.5 mm wire for main circuit (6 points in each circuit)		55 Nos	
20	Supply and installation of UPS Power Point at each workstation comprises of one 5 amp Modular Switch, Two 5 amp Sockets, Gang Box Modular, Face Plate Red/Black/Green for Phase Neutral, Earth respectively in PVC/Flexible conduits.		12 Nos	
21	Supply and installation of RAW point in each row comprises of " One 15 amp Modular Switch , one 15 amp Sockets, Gang Box, Modular Face Plate, M/cB 25 AMP, Cu lugs ISI PVC insulated 4 mm Cu cable Red/Black/Green for phase Neutral , Earth respectively in PVC/ flexible conduits.		5 Nos.	
22	Labour Charges (including testing and handing over)			

UPS Wiring Diagram

